



Service Quote

Client: Fraser Water System
Project: Fraser WTP Magmeter

Browns Hill Job #: 19-023 SQ01
Quote Date: March 4, 2019

Subject: Browns Hill Engineering & Controls, LLC herein proposes to furnish instrumentation, control systems and electrical equipment specifically listed in the following "Scope of Work."

Scope of Work:

Fraser WTP Magmeter

- Provide/Install 6" Diameter Rosemount Magmeter with Remote Transmitter
- Transmitter Mounted on Door of PLC Enclosure
- Start-up Magmeter, Set Flow Totalizer for Forward Flow with 1,000 Gal per Pulse
- Utilize Existing Spare AI for Flowrate
- Utilize Existing Spare DI for Flow Totalizer Pulse
- Program PLC to Scale Flowrate and Track Totalizer Pulses
- Add Flowrate and Totalizer to SCADA Computer
- Provide Updated PLC Wiring Diagrams
- Provide O&M

Only items listed on this scope of work are included in this pricing.

Exclusions: The following items are specifically excluded from this scope of work:
- All costs associated with cutting, patching and painting

Browns Hill Engineering & Controls, LLC agrees to perform all work described per this proposal for the following lump sum price.

Proposal lump sum cost
\$12,247 and no/100 dollars

This proposal is valid for 30 days and subject to revision after that time.

We are now accepting all major credit cards.

We appreciate the opportunity to provide this proposal and should you have any questions please contact the undersigned at 720-344-7771.

Sincerely,

Browns Hill Engineering & Controls, LLC

Customer Approval:

Signature: _____

Date: _____

Name: _____